

DOUGLAS AVENUE PROJECT BID TAB

Updates: 02/06/19

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED
201-00000	CLEARING AND GRUBBING	LS	1	\$	\$
202-00026	REMOVE CONCRETE DITCH PAVEMENT	SY	160	\$	\$
202-00035	REMOVE PIPE	LF	310	\$	\$
202-00047	REMOVE ELECTRICAL EQUIPMENT	LS	1	\$	\$
202-00210	REMOVE CONCRETE PAVEMENT	SY	3	\$	\$
202-00220	REMOVE ASPHALT MAT	SY	44	\$	\$
203-00010	UNCLASSIFIED EXCAVATION	CY	3,121	\$	\$
206-00200	STRUCTURAL BACKFILL (CLASS 2)	CY	43	\$	\$
206-01000	BED COURSE MATERIAL	CY	38	\$	\$
208-00001	SILT DIKE	LF	55	\$	\$
208-00008	EROSION LOG TYPE 1 (9 INCH)	LF	55	\$	\$
208-00011	EROSION BALES (WEED FREE)	EA	10	\$	\$
208-00020	SILT FENCE	LF	1,610	\$	\$
208-00033	SEDIMENT TRAP	EA	2	\$	\$
208-00041	ROCK CHECK DAM	EA	50	\$	\$
208-00045	CONCRETE WASHOUT STRUCTURE	EA	1	\$	\$
208-00051	STORM DRAIN INLET PROTECTION (TYPE 1)	EA	20	\$	\$
208-00070	VEHICLE TRACKING PAD	EA	1	\$	\$
208-00103	REMOVAL AND DISPOSAL OF SEDIMENT (LABOR)	HR	120	\$	\$
208-00207	EROSION CONTROL MANAGEMENT	DAY	20	\$	\$
210-00011	RESET MAILBOX STRUCTURE (TYPE 1)	EA	2	\$	\$
210-01000	RESET FENCE	LF	120	\$	\$
210-02900	RELAY RIPRAP	CY	8	\$	\$
210-04010	ADJUST MANHOLE (SAN SEWER)	EA	6	\$	\$
210-04050	ADJUST VALVE BOX (WATER)	EA	5	\$	\$
212-00006	SEEDING NATIVE	AC	0.27	\$	\$
213-00002	MULCHING (WEED FREE HAY)	AC	0.27	\$	\$
216-00201	SOIL RETENTION BLANKET (CLASS 1)	SY	232	\$	\$
304-06007	AGGREGATE BASE COURSE (CLASS 6) (6 INCH)	CY	1,009	\$	\$
304-09100	AGGREGATE BASE COURSE (RECYCLED ASPHALT PAVEMENT)	TN	501	\$	\$
403-33742	HOT MIX ASPHALT PAVEMENT (GRADING S) (75) (pg 64-22) (2 INCH)	SY	7,482	\$	\$
403-34742	HOT MIX ASPHALT PAVEMENT (GRADING SX) (75) (pg 64-22) (2 INCH)	SY	6,020	\$	\$
506-00212	RIPRAP (12 INCH)	CY	89	\$	\$
507-00100	CONCRETE SLOPE AND DITCH PAVING (REINF) (4 INCH)	CY	214	\$	\$
601-01050	CONCRETE CLASS B (HEADWALL)	CY	4	\$	\$
602-00000	REINFORCING STEEL (HEADWALL)	LB	166	\$	\$
603-01185	18 INCH RCP (CIP)	LF	100	\$	\$
603-01245	24 INCH RCP (CIP)	LF	118	\$	\$
603-05024	24 INCH RCES	EA	1	\$	\$
603-50018	18 INCH HDPE (CIP)	LF	412	\$	\$
620-00020	SANITARY FACILITY	EA	1	\$	\$
625-00000	CONSTRUCTION SURVEYING	LS	1	\$	\$
626-00000	MOBILIZATION	LS	1	\$	\$
627-00005	EPOXY PAVEMENT MARKING	GAL	40	\$	\$
627-30410	PREFORMED THERMOPLASTIC PAVEMENT MARKING (STOP LINE)	SF	32	\$	\$
630-80000	TRAFFIC CONTROL	LS	1	\$	\$
700-70380	EROSION CONTROL	FA	1	\$	\$
700-70010	F/A MINOR CONTRACT REVISIONS	FA	1	\$	\$

GRAND TOTAL \$